The Maryland National Capital Park and Planning Commission

LAYTONIA RECREATIONAL PARK 30% FACILITY PLAN UPDATE SET

7300 AIRPARK ROAD, GAITHERSBURG, MARYLAND, 20879



DPS SHEET#	SHEET#	DESCRIPTION
	C-001	COVER SHEET
	C-100	GENERAL DEVELOPMENT PLAN
	LN-101	NRI/FSD
	LN-102	NRI/FSD
	LN-103	NRI/FSD
	FCP-1	FINAL FOREST CONSERVATION PLAN
	FCP-2	FINAL FOREST CONSERVATION PLAN
	FCP-3	FINAL FOREST CONSERVATION PLAN
	FCP-4	FINAL FOREST CONSERVATION PLAN
	FCP-5	FINAL FOREST CONSERVATION PLAN
	FCP-6	FINAL FOREST CONSERVATION PLAN
	FCP-7	FINAL FOREST CONSERVATION PLAN
	SWM-1	SWM-CONCEPT OVERALL PLAN
	SWM-2	SWM CONCEPT PLAN
	SWM-3	SWM CONCEPT PLAN
	SWM-4	SWM CONCEPT PLAN
	SWM-5	SWM-POST DEV. DRAINAGE AREAS
	ESC-1	ESC CONCEPT PLAN

INDEX OF DRAWINGS

IT IS THE RESPONSE PERMITS PRIOR					
TYPE OF PERMIT	REQ'D	NOT REQ'D	PERMIT#	EXPIRATION DATE	WORK RESTRICTION DATES
MCDPS Floodplain District					
Waterway/Wettand(s)					
Corps of Engineers					
MDE					
MDE Water Quality Certification					
MDE Dam Safety					
N.P.D.E.S. NOTICE OF INTENT					
Site Access Permit					
Others (list)					

.. r shall call "Miss Utility" at 1-800-257-7777, 48 hours prior to the start of work. The Contractor is

DATE REQUESTED	DATE RECEIVED	SHOWN ON PLANS (Y/N)	RELOCATION REQ (Y/N)
 			
-			
	DATE REQUESTED	DATE REQUESTED DATE RECEIVED	

UTLITY STATEMENT
THE ABOVE UTILITY COMPANIES HAVE BEEN CONTACTED REGARDING EXISTING UTILITIES WITHIN
THIS PROJECT AREA, AND INFORMATION SHOWN ON THESE DRAWNOS WAS OBTAINED FROM
AVAILABLE RECORDS, HENCE, ANY UTILITY MODIFICATIONS REQUIRED BY THIS PROJECT HAVE SEEN
COORDINATED WITH THE APPROPRIATE UTILITY COMPANIES. THIS STATEMENT DOES NOT RELIEVE
THE CONTRACTOR OF THEIR RESPONSIBILITY FOR RELD LOCATING AND VERIFYING ALL
UNDERGROUND UTILITIES PRIOR TO STARTING CONSTRUCTION.

	MONTGOMERY COU PERMITTING SERVICES		NOTE: MCDPS APPROVAL DOES NOT NEGAT THE NEED OF A MCDPS ACCESS PERMIT.
	Stormwater Management:	Sediment Control Technical Requirements	Administrative Requirements:
APPROVED FOR PROCUREMENT		Raviewed Date	Reviewed Date SEPARANT CONTROL PERMIT NO.
roved By: Date:	Raviowed Data	Approved Date	
arrays are are represented and second	Approved Date		MCDPS APPROVAL OF THIS PLAN WILL EXPIRE ONE YEAR PROM

HURON CONSULTING	DESIG	N		Professional Certification . I hereby certify that	
Designer's Name 20410 CENTURY BLVD. SUITE 230	DANA WILDER		DLW	these documents were prepared or approved by me, and that I am a duty licensed professional engineer under the laws of the State of Maryland.	
Address	Project Engineer JASON AZAR	Date	Checked By: JA	ongricor and an inclusion and one of the state of the sta	
GERMANTOWN, MD 20874 City/State/Zip	Project Manager RICHARD HURNEY	Date	Checked By: REH	License No	
301-528-2010	Principal	Date	Checked By:	Expiration Date	

ADA COMPLIANCE CERTIFICATION



Design Engineer Signature

The Maryland-National Capital Park and Planning Commission ntgomery County Department of Parks 9500 Brunett Avenue Silver Spring, Maryland 20901 (301) 495-2535

ISSUEI	FORF	JLAYTONI	
-		REVISIONS	
Rev. No.	Date	Description	1
			1
			1
			4
]
1			i
			SCALE: AS SHOWN
	-	-	

AYTONIA RECREATIONAL PARK **COVER SHEET**


C-001


Liber 14440 Folio 234 SHT. # 1 of XX


GENERAL NOTES


- Detail drawings and schedules describe construction at given areas. The Gene and all subcontractors shall utilize equivalent construction methods in all areas.
- All notes shown on the drawings shall be assumed as typical unless other
- It shall be the duty of the contractor to verify all dimensions and conditions given on the
- The General Contractor shall be responsible for any and all items required to provide a site uctions (above and below grade) and rough grade to specified eleva
- To All Bidders: The General Contractor and all major subcontractors shall visit the site to
- Any work within the public right-of-way, shall be performed in accordance with the latest MCDPWT standards and specification. This work includes, but not limited to: Repairing; Restoring; and obtaining final inspection approvals.
- Prior to vegetative stabilization, all disturbed areas must be topsoiled per the Montgomery County "Standards and Specifications for Topsoil" (see DPS sheet 4 of 8) and MNCPPC Technical Specifications. If on-site materials do not meet requirements of topsoil, coordinate with M-NCPPC regarding filling-in of certified composit to on-site soils in order to meet
- cies, omissions, ambiguities, or conflicts in or among the constructio Any decrepances, or insectine, amaginates, or contacts in or among one construction documents or doubt about their meaning, shall be brought to the attention of the MNCPPC Construction Manager for direction before proceeding with work. If ambiguities exist, the better quality and greater quantity of work shall be bid upon and installed by the Contractor unless otherwise indicated by the MNCPPC's Construction Manager in writing.

ATER MANAGEMENT CERTIF	IOA IION -		
CERTIFICATION OF THE QUANTITIES			
"I hereby certify that the amount of excavation has been computed to	excavation, cubic yards of		
Signature	Date		
Printed Name	Registration Number		
Note: The earthwork cut and fill quantities and indicated in this certificate are calculated for the should not be used for contractual obligations	he purpose of plan Approval and		
MAINTENANCE CE	RTIFICATION		
"I/we hereby certify that I/we assume mainter stormwater management structures shown he responsibility is legally transferred, I/we agree Countly Department of Environmental Protect (signed by both parties) transferring said maintime." Data Open Open (Developer,	ereon. If maintenance a to supply the Montgomery ion with a copy of the document		
	CERTIFICATION OF The Thereby certify that the amount of excavation has been computed to		











Columbia, MD 21046

City/State/Zip 301-362-9200

N. Oso. Kadke BUTHO

NIKKI RADKE STRAUGHAN ENVIRONMENTAL SERVICES, INC.




Park and Planning Commission Montgomery County Department of Parks 9500 Brunett Avenue Silver Spring, Maryland 20901 (301) 495-2535

	-		REVISIONS	LATION
	Rev. No.	Date	Description	
Project Manager Date	1	5/13/10		
Construction Manager Date	. 2	01/8/3		
	3	6/10/10		·
Park Manager Date	1			
				SCALE: AS SHOWN
	Project Manager Date Construction Manager Date	Project Manager Date 1 Construction Manager Date 2 3 3	Project Manager Date 1 S1310 Construction Manager Date 2 6810 3 eriorio 3 eriorio	REVISIONS Rev. No. Date Description Project Manager Date 1

Final Forest

FCP - 1 Conservation Plan

Liber 14440 Folio 234 26063 491 SHT. # 1 of 7



City/State/Zip

Columbia, MD 21046

301-362-9200

N: Oca: Vadke 6/17/10 NIKK! RADKE STRAUGHAN ENVIRONMENTAL SERVICES, INC



Park and Planning Commission Montgomery County Department of Parks 9500 Brunett Avenue Silver Spring, Maryland 20901

(301) 495-2535


REVIEW AND APPROVAL				1100011000111 011	31 A Y	IUNI
				REVISIONS	1222	T OTAT
		Hav. No.	Date	Description	1	
Project Manager	Date	1	5/13/10		1	
Construction Manager	Date	2	6/8/10		1	(
	52.0	3	6/10/10			•
Park Manager	Date]	
					SCALE: AS	S SHOWN

Final Forest Conservation Plan

FCP - 2

Liber 14440 Folio 234

SHT. # 2 of 7



Silver Spring, Maryland 20901 (301) 495-2535

Conservation Plan

Liber 14440 Folio 234 26063 491


SHT. # 3 of 7


NIKKI RADKE STRAUGHAN ENVIRONMENTAL SERVICES, INC

City/State/Zip

301-362-9200

elephone Number





Columbia, MD 21046

Talephone Number

Nilse: Kadke 6/17/10 NIKKI RADKE STRAUGHAN ENVIRONMENTAL SERVICES, INC



Park and Planning Commission Montgomery County Department of Parks 9500 Brunett Avenue Silver Spring, Maryland 20901 (301) 495-2535

-	REVIEW AND APPROVAL		10000		TOODITEMENT OR	JLA YTONIA
					REVISIONS	TENTION
1			Hav. No.	Date	Description	7
-	Project Manager	Date	1	5/13/10]
-	Construction Manager	Date	2	5/8/10		
-	<u></u>		3	6/10/10		
1	Park Manager	Date				
						SCALE: AS SHOWN

Liber 14440 Folio 234 26083 491

Final Forest Conservation Plan

FCP - 5 SHT. # 5 of 7

REFORESTATION INSPECTION AND PLANTING NARRATIVE

. REFORESTATION INSPECTION SCHEOULE THERE SHALL BE FIVE INSPECTIONS FOR FOREST CONSERVATION.

A. THE FIRST INSPECTION SHALL OCCUR AFTER FLAGGING/STAKING OF THE L.O.D. AND/OR STREAM BUFFERS, AND PRIOR TO ANY CLEARING, GRADING OR SEDIMENT CONTROL MEASURES. THIS INSECTION IS TO ADDRESS THE ISSUES OF TREE PROTECTION AND SEDIMENT CONTROL. THE OEVELOPER, ARBORIST AND REPRESENTATIVES FROM MNCPPC AND MCDEP WILL MEET TO WALK THE PROPOSED UNITS OF DISTURBANCE AND DETERMINE THE FINAL LOCATIONS OF SEDIMENT CONTROL DEVICES AND TREE PROTECTION DEVICES.

. THE SECOND INSPECTION SHALL OCCUR AFTER PLACEMENT OF SEDIMENT CONTROL DEVICES AND TREE PROTECTION DEVICES, AND PRIDR TO CLEARING AND GRADING. THIS INSPECTION IS TO DETERMINE THE COMPLETION AND ADEQUACY OF PROTECTIVE MEASURES.

C. THE THIRD INSPECTION SHALL OCCUR PRIOR TO PLANTING IN REFORESTATION AREAS. THIS PRE-PLANTING INSPECTION IS TO MAKE FINAL DECISIONS REGARDING THE BEST IMPLEMENTATION OF THE PLANTING PLAN, INCLUDIN BUT NOT LIMITED TO, THE FINAL PLACEMENT AND SELECTION OF PLANT SPECIES, DETERMINATION OF THE REGENERATION POTENTIAL OF EXISTING PLANTS TO REMAIN, AND A DETERMINATION OF THE BEST EDGE PLANTING TREATMENT. THE PURCHASE AND DELIVERY OF PLANT MATERIALS SHOULD NOT BE MADE UNTIL AFTER THIS NSPECTION, SINCE A DETERMINATION MAY BE MADE IN THE FIELD TO ALTER THE CHOICE OF PLANT MATERIAL

D. THE FOURTH INSPECTION SHALL OCCUR IMMEDIATELY FOLLOWING THE COMPLETION OF THE REFDRESTATION PLANTING. THIS INSPECTION IS TO DETERMINE THE COMPLETION AND ADEQUACY OF THE PLANTING.

E. THE FIFTH AND FINAL INSPECTION SHALL OCCUR TWO YEARS AFTER INSTALLATION OF THE PLANTINGS. THE PURPOSE OF THIS INSPECTION IS TO DETERMINE THE SUCCESS OF PLANTINGS AND ADEQUACY OF THE MAINTENANCE PROGRAM FOR RELEASE OF THE BOND AND TO DETERMINE WHETHER ADDITIONAL PLANTINGS AND A FURTHER

2. PRE-PLANTING CONSIDERATIONS

A. IN AREAS WITH SUBSTANTIAL GROWTH OF INVASIVE GROWNO COVER SPECIES. MEASURES SHALL BE TAKEN TO REMOVE AND CONTROL INVASIVES. THE INFESTED AREAS SHOULD BE MOWN PRIOR TO COMMENCEMENT OF PLANTING NECESSARY WEED CONTROL MEASURES SHOULD BE DETERMINED DURING THE PRE-PLANTING INSPECTION, INCLUDING, BUT NOT LIMITED TO, MULCHING, PERIODIC MOWING AROUND THE REFORESTATION PLANTINGS, AND FABRIC COVERINGS THE USE OF CHEMICAL WEED CONTROLS WILL BE LIMITED TO EXTREME CASES AND ONLY WITH PRIOR WRITTEN APPROVAL BY MNCPPC STAFF. WHERE PERIODIC MOWING WILL OCCUR AS A WEED CONTROL MEASURE, THE TYPICAL TREE PLANTING DISTRIBUTION PATTERN SHOULD BE MODIFIED SO AS TO ALLOW ACCESS BY MOMING EQUIPMENT

B. A SOILS ANALYSIS WILL BE CONDUCTED PRIOR TO COMMENCEMENT OF REFORESTATION. ON LAND WHERE EXTENSIVE AGRICULTURAL USE HAS DCCURRED IN THE PAST, TEST PITS WILL BE DUG IN AREAS OF UNDISTURBED SOIL TO DETERMINE IF A FRAGIPAN LAYER IS PRESENT, IF FRAGIPAN IS YESENT, IT SHOULD BE PIERCEO BY AUGURING AND PLANTING HOLES SHOULD BE DUG TO TWICE THE NORMAL DIAMETER FOR THE MATERIAL PLANTED.

C. SOILS SHOULD BE TREATED BY INCORPORATING NATURAL MULCH WITHIN THE TOP 12 INCHES, OR AMENDMENTS AT DETERMINED BY THE SOILS ANALYSIS. NATURAL AMENDMENTS, SUCH AS ORGANIC MULCH OR LEAF MOLD COMPOST

D. IF FILL MATERIAL IS USED AT THE PLANTING SITE, IT SHOULD BE CLEAN FILL WITH 12 INCHES OF NATIVE SOIL. STOCKPILING OF NATIVE TOP SOILS MUST BE DONE IN SUCH A WAY THAT THE HEIGHT OF THE PILE DOES NOT OAMAGE THE SEED BANK.

3. PLANT AMENDMENT MATERIAL STORAGE

IT IS RECOMMENDED THAT PLANTING OCCUR WITHIN 24 HOURS OF DELIVERY TO THE SITE. PLANT MATERIALS WHICH ARE LEFT UNPLANTED FOR MORE THAN 24 HOURS SHOULD BE PROTECTED FROM DIRECT SUN AND WEATHER AND KEPT MOIST. NURSERY STOCK SHOULD NOT BE LEFT UNPLANTED FOR MORE THAN TWO (2) WEEKS.

PRIOR TO PLANTING, PLANTING STOCK SHOULD BE INSPECTED. PLANTS NOT CONFORMING TO STANDARD NURSERYMAN SPECIFICATIONS FOR SIZE, FORM, VIGOR, ROOTS, TRUNK WOUNDS, INSECTS, AND DISEASE SHOULD BE REPLACED.

5. PLANTING SPECIFICATIONS

A, CONTAINER GROWN STOCK: SUCCESSFUL PLANTING OF CONTAINER GROWN STOCK REQUIRES CAREFUL SITE PREPARATION AND INSPECTION OF THE PLANT MATERIAL ROOT SYSTEM. CAUTION IS RECOMMENDED WHEN SELECTING PLANTS GROWN IN A SOILS MEDIUM DIFFERING FROM THAT OF THE PLANTING SITE. THE PLANT SHOULD BE REMOVED FROM THE CONTAINER AND THE ROOTS GENTLY LOOSENED FROM THE SOILS. IF THE ROOTS ENCIRCLE THE ROOT BALL, SUBSTITUTION IS STRONGLY RECOMMENDED. J-SHAPED OR KINKED ROOT SYSTEMS SHOULD ALSO BE NOTED AND SUBSTITUTED IF NECESSARY. ROOTS MAY NOT BE TRIMMED ON-SITE, OUE TO THE INCREASED CHANCES OF SOIL BORNE DISEASES. THE PLANTING FIELD SHOULD BE PREPARED AS SPECIFIED. NATIVE STOCKPILED SOILS SHOULD BE USED TO BACKFILL PLANTING FIELD. RAKE SOILS EVENLY OVER THE PLANTING FIELD AND COVER WITH A

9. BALLED AND BURLAPPED TREES: BALLED AND BURLAPPED TREES MUST BE HANDLED WITH CARE WHILE PLANTING TREES SHOULD NOT BE PICKED UP BY THE TRUNK OR DROPPED. AS BOTH PRACTICES WILL TEND TO SEPARATE THE TRUNK FROM THE ROOT BALL. PRIOR TO PLANTING, ROOT BALLS SHOULD BE KEPT MOIST.

C. PLANTING FIELDS SHOULD BE CREATED EQUAL TO 2.5 TIMES THE DIAMETER OF THE ROOT BALL. USE WATERING TO SETTLE SOIL BACKFILLED AROUND TREES. STOCKPILED NATIVE TOP SOILS, IF AVAILABLE, SHOULD BE USED TO BACKFILL THE PLANTING FIELD. AMENDMENTS ARE NOT RECOMMENCED IN THE PLANTING FIELD. AS STUDIES HAVE SHOWN THAT ROOTS WILL BE ENCOURAGED TO STAY WITHIN THE AMENDED SOILS. SOILS SHOULD BE RAKED EVENL OVER THE PLANTING FIELD AND COVERED WITH 2 TO 4 INCHES OF MULCH.

D. STAKING OF TREES IS NOT RECOMMENDED EXCEPT IN AREAS OF HIGH WINDS. MOVEMENT IS NECESSARY TO STRENGTHEN THE TRUNK OF THE PLANTED TREE. IF STAKES ARE USED, THEY SHOULD BE REMOVED AFTER THE FIRST GROWING SEASON. WRAPPING IS ALSO NOT RECOMMENDED DUE TO THE INCREASED OPPORTUNITIES FOR

5. POST-PLANTING CONSIDERATIONS

A. SOIL STABILIZATION: FOR AREAS OF LARGE-SCALE DISTURBANCE, SOILS MUST BE STABILIZED USING A NON-TURF-BUILDING GROUND COVER OR ENGINEERING FABRIC.

B. PROTECTIVE DEVICES: TO PREVENT DAMAGE OF PLANTED AREAS, ALL REFORESTATION AND AFFORESTATION SITES MUST BE POSTED WITH APPROPRIATE SIGNS AND FENCEO. CONSTRUCTION EQUIPMENT SHALL BE PROHIBITED IN

SEQUENCE OF EVENTS FOR PROPERTY OWNERS REQUIRED TO COMPLY WITH FOREST CONSERVATION AND/OR TREE-SAVE PLANS

1. AN ON-SITE PRE-CONSTRUCTION MEETING IS REQUIRED AFTER THE LIMITS OF DISTURBANCE HAVE BEEN STAKED AND FLAGGED, BUT BEFORE ANY CLEARING OR GRADING BEGINS. THE PROPERTY OWNER SHOULD CONTACT THE MONITGOMERY COUNTY PLANNING DEPARTMENT INSPECTION STAFF BEFORE CONSTRUCTION TO VERIFY THE LIMITS OF DISTURBANCE AND DISCUSS TREE PROTECTION AND TREE CARE MEASURES. THE DEVELOPER'S REPRESENTATIVE, CONSTRUCTION SUPERINTENDENT, ISA CERTIFIED ARBORIST OR MARYLAND-LICENSED TREE EXPERT THAT WILL IMPLEMENT THE TREE PROTECTION MEASURES, FOREST CONSERVATION INSPECTOR, AND DEPARTMENT OF PERMITTING SERVICES (DPS) SEDIMENT CONTROL INSPECTOR SHOULD ATTEND THIS PRE-CONSTRUCTION MEETING.

NO CLEARING OR GRADING SHALL BEGIN BEFORE STRESS-REDUCTION MEASURES HAVE BEEN IMPLEMENTED. APPROPRIATE MEASURES MAY INCLUDE, BUT ARE NOT LIMITED TO:

I. ROOT PRUNING

- II. CROWN REDUCTION OR PRUNING
- III. WATERING IV FERTILIZING
- V. VERTICAL MULCHING
- VI. ROOT AERATION MATTING

MEASURES NOT SPECIFIED ON THE FOREST CONSERVATION PLAN MAY BE REQUIRED AS DETERMINED BY THE FOREST CONSERVATION INSPECTOR IN COORDINATION WITH THE ARBORIST.

3. A MARYLAND-LICENSED TREE EXPERT OR AN INTERNATIONAL SOCIETY OF ARBORICULTURE- CERTIFIED ARBORIST MUST PERFORM ALL STRESS REDUCTION MEASURES, DOCUMENTATION OF STRESS REDUCTION MEASURES WHIST BE EITHER OBSERVED BY THE FOREST CONSERVATION INSPECTOR OR SENT TO THE INSPECTOR AT 8787 GEORGIA AVENUE SILVER SPRING, MD 20910. THE FOREST CONSERVATION INSPECTOR WILL DETERMINE THE EXACT METHOD TO CONVEY THE STRESS REDUCTIONS MEASURES DURING THE PRE-CONSTRUCTION MEETING.

A TEMPORARY TREE PROTECTION DEVICES SHALL BE INSTALLED PER THE FOREST CONSERVATION PLANTREE SAVE PLAN AND PRIOR TO ANY CONSTRUCTION ACTIVITIES, TREE PROTECTION FENCING LOCATIONS SHOULD BE STAKED PRIOR TO THE PRE-CONSTRUCTION MEETING. THE FOREST CONSERVATION INSPECTOR, IN COORDINATION WITH THE DPS SEDIMENT CONTROL INSPECTOR, MAY MAKE FIELD ADJUSTMENTS TO INCREASE THE SURVIVABILITY OF TREES AND FOREST SHOWN AS SAVED ON THE APPROVED PLAN. TEMPORARY TREE PROTECT DEVICES MAY INCLUDE:

A. CHAIN LINK FENCE (FOUR FEET HIGH)

B. SUPER SILT FENCE WITH WIRE STRUNG BETWEEN SUPPORT POLES (MINIMUM 4 FEET HIGH) WITH HIGH VISIBILITY

C. 14 GAUGE 2 INCH X 4 INCH WELDED WIRE FENCING SUPPORTED BY STEEL T-BAR POSTS (MINIMUM 4 FEET HIGH) WITH HIGH VISIBILITY FLAGGING.

5. TEMPORARY PROTECTION DEVICES SHALL BE MAINTAINED AND INSTALLED BY THE CONTRACTOR FOR THE DURATION OF CONSTRUCTION PROJECT AND MUST NOT BE ALTERED WITHOUT PRIOR APPROVAL FROM THE FOREST CONSERVATION INSPECTIOR. NO EQUIPMENT, TRUCKS, MATERIALS, OR DEBRIS MAY BE STORED WITHIN THE TREE PROTECTION FENCE AREAS DURING THE ENTIRE CONSTRUCTION PROJECT, NO VEHICLE OR EQUIPMENT ACCESS TO THE FENCED AREA WILL BE PERMITTED. TREE PROTECTION SHALL NOT BE REMOVED WITHOUT PRIOR APPROVAL OF FOREST CONSERVATION INSPECTOR.

6. FOREST RETENTION AREA SIGNS SHALL BE INSTALLED AS REQUIRED BY THE FOREST CONSERVATION INSPECTOR, OR

7. LONG-TERM PROTECTION DEVICES WILL BE INSTALLED PER THE FOREST CONSERVATION PLAN/TREE SAVE PLAN AND ATTACHED DETAILS. INSTALLATION WILL OCCUR AT THE APPROPRIATE TIME DURING THE CONSTRUCTION PROJECT. REFER TO THE PLAN DRAWING FOR LONG-TERM PROTECTION MEASURES TO BE INSTALLED.

DURING CONSTRUCTION

POST-CONSTRUCTION

8. PERIODIC INSPECTIONS BY THE FOREST CONSERVATION INSPECTOR WILL OCCUR DURING THE CONSTRUCTION PROJECT. CORRECTIONS AND REPAIRS TO ALL TREE PROTECTION DEVICES, AS DETERMINED BY THE FOREST CONSERVATION INSPECTOR, MUST BE MADE WITHIN THE TIMEFRAME ESTABLISHED BY THE INSPECTOR.

9. AFTER CONSTRUCTION IS COMPLETED, AN INSPECTION SHALL BE REQUESTED. CORRECTIVE MEASURES MAY INCLUDE:

- A REMOVAL AND REPLACEMENT OF DEAD AND DYING TREES
- B. PRUNING OF DEAD OR DECLINING LIMBS C. SOIL AERATION
- D. FERTILIZATION
- E. WATERING
- F. WOUND REPAIR

G. CLEAN UP OF RETENTION AREAS

10. AFTER INSPECTION AND COMPLETION OF CORRECTIVE MEASURES HAVE BEEN UNDERTAKEN, ALL TEMPORARY PROTECTION DEVICES SHALL BE REMOVED FROM THE SITE. REMOVAL OF TREE PROTECTION DEVICES THAT ALSO OPERATE FOR EROSION AND SEDIMENT CONTROL MUST BE COORDINATED WITH BOTH THE DEPARTMENT OF PERMITTING

CONSERVATION INSPECTOR. NO ADDITIONAL GRADING, SODDING, OR BURIAL MAY TAKE PLACE AFTER THE TREE PROTECTION FENCING IS REMOVED.

NOTES FROM APPROVED NRI

- THERE ARE NO READILY OBSERVABLE RARE, THREATENED OR ENDANGERED SPECIES OR CRITICAL HABITATS ON THIS SITE.
- THERE ARE RECORDS OF HISTORIC OR CULTURAL RESOURCES ON THIS SITE. THE DAVID GRIFFITH FARM CORNCRIB, WILLIAM BASIL MOBLEY FARM TENANT HOUSE ARE DESCRIBED IN THE LAYTONIA RECREATION PARK FACILITY PLAN - OCTOBER 2001 THE REPORT SUGGESTS THAT NONE OF THESE STRUCTURES ARE ELIGIBLE FOR LISTING IN THE NATIONAL REGISTER OF HISTORIC PLACES.
- THERE ARE NO MONTGOMERY COUNTY OR STATE CHAMPION TREES ON THIS PARCEL. NO TREES ON THE PARCEL HAVE A DBH ≥ 75% OF THE COUNTY OR STATE CHAMPION.
- THERE IS NO FLOODPLAIN ASSOCIATED WITH THIS PROPERTY
- THIS SITE IS LOCATED WITHIN THE UPPER ROCK CREEK SPA

ENVIRONMENTAL SUMMARY

ACREAGE OF TRACT	48.10
ACREAGE OF TRACT REMAINING IN	0.00
AGRICULTURAL USE	
ACREAGE OF ROAD AND UTILITY ROWS WHICH	0.00
WILL NOT BE IMPROVED AS PART OF THE	
DEVELOPMENT APPLICATION	
ACREAGE OF STREAM VALLEY BUFFER	4.11
ACREAGE OF TOTAL EXISTING FOREST	9.15
ACREAGE OF TOTAL FOREST RETENTION	6.35
ACREAGE OF TOTAL FOREST CLEARED	2.80
LAND USE CATEGORY AND CONSERVATION AND	IDA: 15%/20%
AFFORESTATION THRESHOLDS FROM THE	
SECTION 22A-12(a) OF THE FOREST	
CONSERVATION LAW	
ACREAGE OF FOREST RETAINED, CLEARED, AND	Retained: 0.00
PLANTED WITHIN WETLANDS	Cleare d: 0.00
	Planted: 0.00
ACREAGE OF FOREST RETAINED, CLEARED, AND	Retained: 0,00
PLANTED WITHIN 100-YEAR FLOODPLAINS	Cleared: 0.00
	Planted: 0.00
ACREAGE OF FOREST RETAINED, CLEARED, AND	Retained: 2.42
PLANTED WITHIN STREAM BUFFERS	Cleared: 0.00
	Planted: 0.00
ACREAGE OF FOREST RETAINED, CLEARED, AND	Retained: 0.00
PLANTED WITHIN PRIORITY AREAS	Cleared: 0.00
	Planted: 0.00
LINEAR FEET AND AVERAGE WIDTH OF STREAM	Linear Feet: 400
BUFFER PROVIDED	Avg. Width: 160

	TREES FOR RE	MOVAL	REATER THA	N 30" DBH	
Trees	Species	D.B.H. (inches)	Tree Condition	Critical Root Zone Radius (ft)	Critical Root Zone (sq. ft.)
T66*	Prunus serotina	43	Avg.	64.5	13.069
T67*	Prunus serotina	36	Avg./Poor	54	9.161
T68*	Prunus serotina	32	Good/Avg.	48	7,238
T80*	Acer socchorinium	30	Good/Avg.	45	6,362
T107*	Paulownia tomento	37	Avg.	55.5	9,677
T116*	Tilia cordata	43	Good/Avg.	64.5	13,069

EXISTING SPECIMEN TREES

T66* Prunus serotina 43 Avg.

T68* Prunus serorino 32 Good/Avg.

T80* Acer soccharinium 30 Good/Avg.

T81* Acer soccharinium 38 Good/Avg. r85* Acer sacchurmium 39 Good/Avg.

T103 Acersar charmium 25 Good/Avg.

T98* Acer rebrain 37 Avg.

1107* Paulownia tomentosa 37 Avg.

T132* Robinio pseudoacocia 36 Poor

T166 Robinia pseudoacacio 25 Gaod/Avg.

T17D Platanus occidentalis 28 Good/Avg.

T64 Prunus serotina

T67* Prunus serorino

T104 Acer rubrum
T105 Acer rubrum

T115 Morus alba

T116" Tilia condata

T119 Morus oiba

(inches) Condition 27 Good/Avg.

27 Good/Avg.

28 |Good/Avg.

43 Good/Avg.

FOREST SUMMARY TABLE

FOREST SUMMARY	
	ACRE
FOREST CLEARED	
AREA A	2.
AREA B	0.
TOTAL	2.
FOREST PLANTED	
AREA #1	0.
AREA #2	0.
AREA #3	1.
AREA #4	3.
TOTAL	5.
FOREST RETAINED	6.

SOIL CHARACTERISTICS & LIMITATIONS

FOREST CONSERVATION WORKSHEET Laytonia Recreational Park

HDR 0

MPD

20% xF= 0.00

0.00

0.00

0.00

4B.10

9.62

9.15

1.94

0.00

0.00

6.35

0.00

5.60

5.60

0.00

0.00

NET TRACT AREA:

A. Total tract area .

F. Net Tract Area

G. Afforestation Threshold

H. Conservation Threshold.

EXISTING FOREST COVER

K. Area of forest above conse

PROPOSED FOREST CLEARING

N. Total area of forest to be cleared O. Total area of forest to be retained

S. Total reforestation required

T. Total afforestation required

PLANTING REQUIREMENTS:

1. Existing forest cover

E. Other deductions (specify) ...

8. Land dedication acres (parks, county facility, etc.) ...

LAND USE CATEGORY: (from Trees Technical Manual)

J. Area of forest above afforestation threshold=

L. Forest retention above threshold with no mitigation ...,= M. Clearing permitted without mitigation .

P. Reforestation for clearing above conservation threshold=

Q. Reforestation for cleaning below conservation threshold=

R. Credit for retention above conservation threshold=

U. Credit for landscaping (may not exceed 20% of "S")=

D. Area to remain in commercial agricultural production/use ...

C. Land dedication for roads or utilities (not being constructed by this plan)

ARA MDR IDA 0 0 1

Input the number "t" under the appropriate land use.

Seit Type	Hydric Status	K-Value ³	Prime or Unique Farmiands	Restrictions and Limitation
Gaila (1C)	No	0.37	Familioul of statewide importance	Somewhat limited due to slop and frost action
Glenela (78)	No	0.32	Prane farutand	Somewhat imited due to low strength and frost action
Baile (6A)	(es	0.43	Ne	Very kinited due to frost actio depth to saturated zone, and shrink-swell potential
Оссодизи (17В)	No	9.37	Prime Enoughed	Somewhat landed due to frost action
Blocktown (116D)	No	0.24	No	Very finited due to slope, fros action, and depth to soft bedrock

REFORESTATION SCHEDULE

Size (caliper)	Botanical Name	Common Name	Planting Rate	Approximate Spacing	Quantity Reforestation Area 1	Quantity Reforestation Area 2	Quantity Reforestation Area 3	Quantity Reforestation Area 4	TOTALS
	Deciduous Forest				0.88 acre	0.26 acre	1.06 acre	3.4 acre	6
3/4" - 1"	Prunus serotina	black cherry	200/acre	12' x 15'	25	7	30	97	160
3/4" - 1"	Quercus alba	white oak	200/acre	12' x 15'	25	7	3D	97	160
3/4" - 1"	Quercus phellas	willow oak	200/acre	12' x 15'	25	7	30	97	160
3/4" - 1"	Acer rubrum	red maple	200/acre	12' x 15'	25	7	3D	97	160
3/4" - 1"	Diospyras virginiana	common persimmon	200/acre	12' x 15'	25	7	30	97	160
3/4" - 1"	Liriodendron tulipifera	tuliptree	200/acre	12' × 15'	25	7	30	97	160
3/4" - 1"	Quercus rubra	northern red oak	200/acre	12' x 15'	25	7	30	97	160
					176	52	212	680	1120
	Understory								
3 GAL	ilex opaca	American holly	3D/acre	36' x 40'	5	2	6	20	34
3 GAL	Cercis conadensis	eastern redbud	30/acre	36' x 40'	5	2	6	20	34
3 GAL	Viburnum acerifolium	mapleleaf viburnum	3D/acre	36' x 40'	5	2	6	20	34
3 GAL	Vibumum dentatum	southern arrowwood	30/acre	36' x 40'	5	2	ō	20	34
3 GAL	Amelanchier orborea	serviceberry	3D/acre	36' x 40'	5	2	6	20	34
					26	8	32	102	168

	M-NCPPC outgomery County Planning E Environmental Planning Se APPROVAL FOREST CONSERVATION	ection
	Approved by	Date
01		
02		
03		
04		
05		

Straughan Environmental Services	DESIGN			
Designer's Name 9135 Guilford Rd, Suite 100	Nikki Radke		Justin Haynes	
Address Columbia, MD 21046	Project Engineer	Date	Checked By:	
City/State/Zip	Project Manager	Date	Chacked By:	
301-362-9200	Principal	Data	Checked By:	
Telephone Humber	Consum by	Code	Observed Sur	

N. OBE. Kadke enilino



The Maryland-National Capital Park and Planning Commission


Montgomery County Department of Parks 9500 Brinett Avenue Silver Spring, Marviand 20901 (301) 495-2535

REVIEW AND APPROVAL	ISSUED FOR PROGUREMENT ON			LAYTONIA RECREATIONAL PARK	
	1	REVISIONS		Diri TOTAL TOTAL TANK	r
	Rev. No.	Date	Description		_
Project Manager Date	1	61/2/13		Final Forest	
Construction Manager Date	2	6840		Conservation Plan	
	3	61010		Conservation Fian	
Park Manager Date				Liber 14440 Folio 234	ς

Liber 14440 Folio 234

FCP - 6

SHT. # 6 of 7



NOTES:

- 1. THE BOUNDARIES OF THE LIMITS OF DISTURBANCE SHOULD BE STAKED AND FLAGGED PRIOR TO ERECTING THE PROTECTIVE DEVICE.


 2. AVOID OAMAGE TO GENICAL ROOT ZONES OF TREES. ANCHOR POSTS SHOULD BE PLACED TO AVOID SEVERING OR DAMAGING LARGE TREE ROOTS.

 3. FENCING MATERIAL SHOULD BE FASTENED SECURELY TO THE ANCHOR POSTS WITH FENCE WRE.

 4. FENCE SIGNS, AND THEREFORE, THE TALLER 7 1/Z POSTS, MUST BE PLACED A MINIMUM OF 50' APART AND AT FENCE CORNERS, CONDITIONS ON SITE AFFECTING VISIBILITY MAY WARRANT PLACING SIGNS CLOSER OR FURTHER APART. ATTACHING SIGNS TO TREES IS PROHIBITED.

 5. DEVICE SHOULD BE MAINTAINED THROUGHOUT CONSTRUCTION.


WOVEN WIRE TREE PROTECTION FENCE



SOURCE: STATE FOREST CONSERVATION TECHICAL MANUAL

PLANTING DISTRIBUTION PATTERN

NOT TO SCALE




1. STAKING SHOWN ON THIS DETAIL IS FOR DECIDUOUS AND EVERGREEN TREES UNDER 4" CALIPER AND 6" OR MORE IN HEIGHT. STAKE TREES ONLY IN AREAS OF HIGH WIND. REMOVE AFTER FIRST GROWING SEASON.

2. NO STAKING REQUIRED FOR STREET TREES. CONTRACTOR RESPONSIBLE FOR KEEPING STREET TREES STRAIGHT.

PLANTING DETAIL

NOT TO SCALE



- NOTES:
 1. HEIGHT OF CAGE SHALL BE 4-FEET (MIN.)
 2. CAGE SHALL BE FASTENED TO STAKE WITH TWO (MIN.)
 11-INCH RELEASABLE CABLE TIES (ONE AT TOP AND ONE
- 11-INCH RELEASABLE CABLE TIES (ONE AT TOP AND ONE 6" (MIN) ABOVE THE GROUND.


 3. DO NOT DAWAGE TREE DURING INSTALLATION.

 4. DEER BARK PROTECTORS (ITEM #59-80, BY A.M. LEONARD, OR EQUAL) MAY 9E SUBSTITUTIONS MUST BE APPROVED BY FOREST ECOLOGIST.

 5. CAGES TO BE REMOYED AT DIRECTION OF FOREST ECOLOGIST.

 6. ENSURE CAGE IS SECURE TO GROUND TO PREVENT UPLIFT BY DEER.


DEER PROTECTION FENCING DETAIL



SOURCE: STATE FOREST CONSERVATION TECHNICAL MANUAL

TREE PROTECTION CONSTRUCTION SIGNS


NOT TO SCALE




NOTE: TREE PROTECTION SIGNAGE MAY NOT BE REMOVED FOR THE LONGER OF 2 YEAR MAINTENANCE OR UNTIL END-USER REMOVES THEM.

2 YEAR TREE PROTECTION SIGN

NOT TO SCALE





ROOT PRUNING DETAIL

	M-NCPPC gomery County Planning Environmental Planning	
r	APPROVAL	
FO	REST CONSERVATION	ON PLAN
	Approved by	Date
01	Approved by	Date
01 02	Approved by	Date
V.	Approved by	Date
02	Approved by	Date

Straughan Environmental Services		DESIGN	
Designer's Name 9135 Guilford Rd, Suite 100	Nikki Radke		Justin Haynes
Address Columbia, MD 21046	Project Engineer Project Manager	Date	Checked By: Checked By:
City/State/Zip 301-362-9200	Principal	Deta	Checked By:
Tslephone Number			

N. Sel. Kadke 6177190



The Maryland-National Capital Park and Planning Commission

Montgomery County Department of Parks 9500 Brunett Avenue Silver Spring, Maryland 20901 (301) 495-2535

ı	REVIEW AND APPROVAL		ISSUE	D FOR F	ROCUREMENT ON	LAYTONL
					REVISIONS	LIII I OLIII
			Rev. No.	Date	Description	
-	Project Manager	Date	1	6/13/10		
-	Construction Manager	Date	2	82/10		
i			3	61910		_
1	Park Manager	Date				
Ì		1				SCALE: AS SHOWN

AYTONIA RECREATIONAL PARK

Final Forest Conservation Plan

Liber 14440 Folio 234 28083 Folio 234 491

FCP - 7

SHT. # 7 of 7

