#### MONTGOMERY COUNTY DEPARTMENT OF PARK AND PLANNING

THE MARYLAND-NATIONAL CAPITAL PARK AND PLANNING COMMISSION Item # 3

8787 Georgia Avenue Silver Spring, Maryland 20910-3760

#### **MEMORANDUM**

DATE:

January 31, 2002

TO:

Montgomery County Planning-Board

VIA:

Joseph R. Davis, Chief Development Review Division

FROM:

Robert A. Kronenberg, RLA

Planning Department Staff

(301) 495-2187

**REVIEW TYPE:** 

Preliminary Plan and Site Plan Review

APPLYING FOR:

LDRC Zone; 72.40 Acres Property

14 Single Family Dwelling Units/Lots

PROJECT NAME: Mandell Property

CASE #:

8-02019

**REVIEW BASIS:** 

Site Plan Review Required in the LDRC Zone, Article 59-D

Site Plan Review Required for waiver request to eliminate the sidewalks

on both sides of the public roads, Subd. Regs. 50-26(h)

ZONE:

**LDRC** 

LOCATION:

Olney

Located on Batchellors Forest Road, approximately 450 feet south of

Olney Sandy Springs Road

**MASTER PLAN:** 

Olney

APPLICANT:

Porten Companies

FILING DATE:

November 20, 2001

**HEARING DATE:** 

January 31, 2002

STAFF RECOMMENDATION: Approval of 14 single-family detached lots in the LDRC Zone with the following conditions:


Standard Conditions dated October 10, 1995, Appendix A 1.


Conditions of approval of the Preliminary Forest Conservation Plan dated July 9, 2. Final Forest Conservation Plan (including grading and tree protection 2001. information) shall satisfy all conditions referenced in the M-NCPPC Environmental Planning Section memorandum dated January 14, 2002, prior to recording plat or DPS issuance of sediment and erosion control permit:

a. No grading within the stream buffers except where shown on approved site plan for stormwater management facilities and outfalls, the single road crossing and necessary utilities;

- b. A maintenance and management plan and agreement shall be included in the final Forest Conservation Plan for the control of invasive and exotic plant species;
- c. The full stream valley buffer, where possible, must be protected with a Category I Conservation Easement.
- 3. Conditions of MCDPS stormwater management concept approval dated January 22, 2002.
- 4. Site, Landscape/Lighting, Forest Conservation and Sediment and Erosion Control Plans subject to review by staff prior to approval of signature set. Prior to signature set approval, the applicant shall provide the following revisions or information to the plans:
  - a. Site Plan signature set to show all easements, limits of disturbance, PUE's, open space, high priority forests and storm drain outlets.
  - b. Site Circulation:
    - i. Roads:
      - a. Applicant to move the private road further away from Batchellor's Forest Road to create a greater landscape buffer between the proposed lots and the road;
      - b. Applicant to relocate and combine the driveways from lots 4 and 5 to the public road through the utility right-of-way;
  - c. Landscape and Lighting Plan to show the following:
    - i. Provide additional landscaping and screening in the front of lot 11 between the private road and Batchellor's Forest Road;
    - ii. Provide islands and a shade tree in the middle of each cul-de-sac;
    - iii. Increase the size of the shade trees to 2.5-3" caliper;
    - iv. Applicant to relocate light poles outside the PUE.
- 5. The services of a licensed arborist shall be retained to evaluate the appropriate measures necessary to ensure the survival of the large and specimen trees proposed to be preserved whose critical root zones will be impacted by construction.
- 6. Prior to recording of the Plats, the applicant shall convey approximately 41 acres of Open Space (Parcels A-D) as shown on the approved Site Plan, to the HOA.

  Dedication of the Open Space Parcels shall be conveyed free of trash and unnatural debris.





#### RELATED ISSUES PERTINENT TO SITE PLAN REVIEW:

# A. Site Plan Waiver for the elimination of sidewalks on both sides of the road [Subdivision Regulation 50-26(h)]:

A waiver is required for the site plan to eliminate the sidewalks on both sides of the proposed public road. In order to approve the waiver of sidewalks, the Planning Board must find that pedestrians will be able to safely use the roadway. Previously, a waiver was granted for an overlength cul-de-sac with the Preliminary Plan #1-01086.


Batchellors Forest Road is an interim rustic road and does not presently have sidewalks to connect to the proposed public road. The minimal amount of pedestrian traffic for 14 lots and the lack of recreational amenities on and off the site further support the request to delete the sidewalks.

M-NCPPC Staff and DPW&T support the waiver request to eliminate sidewalks within the subdivision.

### PROJECT DESCRIPTION: Surrounding Vicinity

The 72.4 acre property consists of three tributaries to the Northwest Branch in the Olney Master Plan Area. The site is located approximately 450 feet south of Olney Springs Road. The site gains access from Batchellor's Forest Road directly across from Emory Church Road.


The adjacent subdivisions (Norbeck Knolls and Plainfield Orchards, Preliminary Plan #1-82151) to the south and east of the site are zoned RE-2 and RC, respectively. The parcels to the north of the property along Batchellor's Forest Road, including Farquar Middle School, are zoned RE-2 as well as the Casey tract across the road. Directly across Batchellor's Forest Road is Trotters Glen Golf Course, which is zoned RC and RE-2.



# PROJECT DESCRIPTION: Site Description

The site contains rolling topography with pockets of steep slopes predominately located adjacent to the three tributaries of Northwest Branch, a Use Class IV stream. The topography is characterized by gently rolling terrain falling approximately 30 to 40 feet in height from the three knolls where the proposed lots will be developed to the three stream valley areas. The property has an unpaved road from Batchellor's Forest Road leading to the rear of the property. The higher elevations are not forested where much of the development is proposed. The clustering of the lots in the open areas and the location of the proposed road near the existing road will result in minimal clearing and increased forest protection.

Slopes near the stream banks exceed 25%.



### **PROJECT DESCRIPTION: Proposal**

The current proposal for Site Plan consists of 14 single-family detached lots, utilizing the cluster method in the LDRC zone. The clustered lots range in size from 87,000 square feet +/- to 92,000 square feet +/-.

There is a single access into the site directly across from Emory Church Road. The entrance to the site from Batchellor's Forest Road, an interim rustic road, contains berms and landscaping to identify the subdivision. A private road stems off of the public road, paralleling Batchellor's Forest Road to serve four of the proposed lots. As stated in the master plan, individual lots are prohibited from direct access onto a main road. Additional screening will buffer the proposed lots and private road from Batchellor's Forest Road. The proposed public road will impact the stream buffer and floodplain at the most-narrow point, following the existing dirt road, and causing the least impact to the environmental areas.

There are 9 lots on the east side of the stream crossing at the end of the cul-de-sac, creating a very close community atmosphere. Three of the lots will have forested buffers in the front yards and back yard. The majority of the lots will be located on the higher elevations overlooking the stream valley buffer. The entire buffer behind the lots will include a forest conservation easement protecting the sensitive areas.

A waiver to sidewalks within the subdivision was reviewed as part of the site plan. Staff and DPW&T support the waiver due to minimal pedestrian traffic within the subdivision and the absence of sidewalks along Batchellor's Forest Road.

The property is exempt from stormwater management for the proposed development as indicated by the Montgomery County Department of Permitting Services (DPS) letter dated January 22, 2002.

## **PROJECT DESCRIPTION: Prior Approvals**

The LDRC zone was written especially for this particular area of the county and the uniqueness of the rural community in Olney. The intent of the zone is to provide rural clustering of lots to retain open space and protect environmentally sensitive areas.

On October 1, 2001, the Planning Board approved Preliminary Plan #1-01086 for the proposed development, with the following conditions:

- 1. Approval under this preliminary plan is limited to a maximum of fourteen (14) units and the applicant shall pay to the Montgomery County Department of Finance the applicable Development Approval Payment (DAP), pursuant to the FY 2002 Annual Growth Policy prior to receipt of building permits.
- 2. Compliance with the conditions of approval for the preliminary forest conservation plan. The applicant must satisfy all conditions prior to recording plat(s) or MCDPS issuance of sediment and erosion control permits.
- 3. Record Plat to provide for dedication of 70 feet of right-of-way on Batchellor's Forest Road.
- 4. Record plat to show delineation of a Category I conservation easement over the area of stream valley buffer and forest conservation areas.
- 5. Access and improvements as required to be approved by MCDPWT prior to recordation of plats(s).
- 6. Record plat to reference all common ingress/egress easements.
- 7. All roads shown on the approved preliminary plan shall be constructed, by the applicant, to the full width mandated by the Approved and Adopted Master Plan, and to the design standards imposed by all applicable road codes.
- 8. Prior to recording of plat(s) Planning Board approval of waiver for over length culde-sac.
- 9. No clearing, grading or recording of plat prior to site plan approval.
- 10. Final location of units to be determined at site plan.
- 11. All road right-of-way shown on the approved preliminary plan shall be dedicated by the applicant, to the full width mandated by the Approved and Adopted Master Plan.
- 12. The Preliminary Plan will remain valid for thirty-seven (37) months from the date of mailing of the Planning Board opinion. Prior to this date, a final record plat must be recorded for all property delineated on the approved preliminary plan, or a request for an extension must by filed.
- 13. The Adequate Public Facility (APF) review for the preliminary plan will remain valid for sixty-one (61) months from the date of mailing of the Planning Board opinion.
- 14. Other necessary easements.
- 15. Prior to submission of Site Plan, applicant to secure written sewer and water category change approval from Montgomery County Department of Environmental Protection.

#### DISCUSSION OF ISSUES

#### ANALYSIS: Conformance to Master Plan

The proposal meets the requirements of the Olney Master Plan. The Master Plan recommends that "rural clustering retain open space by allowing residences to be grouped on a portion of the site and fosters a more cost effective development pattern than linear or scattered residential". The plan provides 14 clustered lots with the remainder of the property to be conveyed to the HOA as open space. The amount of open space provided within the community is also in conformance with the requirements of the LDRC zone.

The Master Plan also directs that "cluster development should occur on a common roadway with individual lot access to public arterial or primary roads denied". The property has a single access point directly off of Batchellors Forest Road with all of the lots gaining access from the proposed public road.

The protection of environmentally sensitive areas is specifically discussed in the Master Plan with regard to stream valleys. The proposed layout and road design reflects the intent of the Master Plan to preserve as much of the site as possible in open space and limit the impact on environmentally sensitive areas. A category I forest conservation easement will be placed on the entire stream valley buffer, where it is not being impacted by the road crossing and utilities.

# ANALYSIS: Conformance to Development Standards

# PROJECT DATA TABLE

Zoning Proposed Use	LDRC 14 Single Family Lots Utilizing the Cluster Development Option	
Gross/Net Tract Area Area within the 100 Year Floodplain	72.4 Acres 1.3 Acres	
Development Standard	Permitted/ Required	Proposed
Maximum Number of Lots (1 unit/5 acre)  Minimum Lot Area (Sq. Ft.):  Setbacks (ft.)	14 40,000	14 87,120
Front yard	50	50
Side yard	17/35 combined	17
Rear yard	35	35
Minimum Lot Width at the Street Line (ft.):	25	25
Minimum Building Height (ft.):	35	35
Maximum Building Coverage (%):	25	25
Open Space (%): Parcel A (9.06 Acres) Parcel B (32.42 Acres) Parcel C (1.00 Acres) Parcel D (0.63 Acres)	60%	60%

#### FINDINGS for Site Plan Review:

- 1. The site plan is consistent with an approved development plan or a project plan for the optional method of development, if required. None is required.
- 2. The site plan meets all of the requirements of the zone in which it is located. See Project Data Table above.
- 3. The locations of the buildings and structures, the open spaces, the landscaping, recreation facilities, and the pedestrian and vehicular circulation systems are adequate, safe and efficient.

### a. Location of Buildings

The layout of the houses is adequate and efficient; the arrangement of the two cluster areas will provide neighborhood identity in an environmentally sensitive rural setting.

The location of the houses as shown on the site plan is conceptual. The precise location and site grading will not be determined until the owner has chosen a specific house type and a house location plan with grading, to be developed by the project engineer.

### b. Open Spaces

The open spaces are generously laid out and provide attractive, efficient and accessible green space for the entire community.

Over 43 acres of the 72.40 acre site will be retained as open space, as required by the LDRC zone, and will be owned and maintained by the HOA. The majority of the open space to be preserved is within environmentally sensitive areas such as stream valley buffers, wetlands and floodplain.

The LDRC zone requires that a minimum of 60% of the site be retained as open space, and the plan indicates that exactly 60% will be preserved on site.

The property is exempt from stormwater management for the proposed development as indicated by the Montgomery County Department of Permitting Services (DPS) letter dated January 22, 2002.

### c. Landscaping and Lighting

The landscaping and lighting provides safety and efficiency for residents and visitors in the rural setting.

Landscaping and screening consists of the formal streetscape treatment of a treelined street for the public road accessing the property. The islands in the cul-desacs will also receive shade trees for an enhanced residential cluster effect. The entrance to the site and the private road access will contain additional screening and berms to provide a buffer between the proposed lots and Batchellors Forest Road. Additional landscaping is not necessary in the areas where natural vegetation will form an edge along the public road.

Proposed street lighting conforms to the Montgomery County guidelines for public roads for type of fixture, spacing, size and height.

- d. Recreation. Not applicable.
  - e. Vehicular and Pedestrian Circulation

Vehicular and pedestrian circulation in general is adequate, safe and efficient.

Vehicular circulation consists of 50 foot-wide public road right-of-way to serve the fourteen lots proposed in the subdivision. The twenty-foot-wide private road stems off the public road to provide access to four lots. A request to waive sidewalks within the subdivision has been reviewed by staff and DPW&T. Staff and DPW&T support the waiver due to minimal vehicular and pedestrian traffic. The absence of recreation amenities on site further supports the waiver request.

4. Each structure and use is compatible with other uses and other site plans and with existing and proposed adjacent development.

The new houses are clustered preserving 60% of the site as open space. The first cluster of lots access the private road near the entrance, and the other cluster of lots is gathered across the stream buffer and around the public cul-de-sac. Each structure and use is compatible with other uses and with existing and proposed adjacent development.

The activity associated with the proposed residential community will not cause any negative effect on adjacent residential uses.

5. The site plan meets all applicable requirements of Chapter 22A regarding forest conservation.

Forest Conservation requirements have been met by the preservation of 29.41 acres of existing forest, with no additional planting obligations required.

A Category I Conservation easement will be placed over the forest conservation and stream valley buffer areas as shown on the Forest Conservation Plan.

#### APPENDIX

- A. Standard conditions dated October 10, 1995
- B. Memorandums from other Divisions/Agencies
- C. Waiver Request from applicant dated October 30, 2001

#### APPENDIX A: STANDARD CONDITIONS OF APPROVAL DATED 10-10-95:

- 1. Submit a Site Plan Enforcement Agreement, Development Program and Homeowners Associations Documents for review and approval prior to approval of the signature set as follows:
  - a. Development Program to include a phasing schedule as follows:
    - 1. Street tree planting must progress as street construction is completed, but no later than 6 months after completion of the units adjacent to those streets;
    - 2. Clearing and grading to correspond to the construction phasing, to minimize soil erosion;
    - 3. Coordination of each section of the development and roads;
    - 4. Phasing of dedications, stormwater management, sediment and erosion control, forest conservation or other features;
- 2. Signature set of site, landscape/lighting, forest conservation and sediment and erosion control plans to include for staff review prior to approval by Montgomery County Department of Permitting Services (DPS):
  - a. Undisturbed stream buffers, except for the single road crossing, stormwater management outfalls and utilities as shown on the site plan;
  - b. Limits of disturbance;
  - c. Methods and location of tree protection;
  - d. Forest Conservation areas;
  - e. Conditions of DPS Stormwater Management Concept approval letter dated January 22, 2002;
  - f. Note stating the M-NCPPC staff must inspect tree-save areas and protection devices prior to clearing and grading;
  - g. The development program inspection schedule.
  - h. Conservation easement boundary
- 3. Forest Conservation Plan shall satisfy all conditions of approval prior to recording of plat and DPS issuance of sediment and erosion control permit.
- 4. No clearing or grading prior to M-NCPPC approval of signature set of plans.

G:\SP\_STAFFRPT\8-02019.doc

#### MONTGOMERY COUNTY DEPARTMENT OF PARK AND PLANNING



THE MARYLAND-NATIONAL CAPITAL PARK AND PLANNING COMMISSION

8787 Georgia Avenue Silver Spring, Maryland 20910-3760

January 17, 2002

Alan Soukup, Watershed Management Division Department of Environmental Protection Watershed Management Division 255 Rockville Pike Rockville, Maryland 20850

Re:

M-NCPPC Planning Board Approval

Mandell Property (1-01086)

Dear Alan:

At the regular Planning Board hearing on Thursday, November 01, 2001, the Montgomery County Planning Board considered Preliminary Site Plan No.1-01086, an LDRC zoned 72.4 acre property located off of Batchellor's Forest Road in Olney, Maryland.

On November 27, 2001, MCDEP granted a conditional approval for W-3 and S-3 for this site under Administrative Delegation Group AD 2001-07. The condition for final approval for categories W-3 and S-3 is as follows:

"Maintain W-6 and S-6 with advancement to W-3 and S-3 conditioned on the Planning Board's approval of a preliminary plan using the LDRC zone cluster option."

In their deliberations, the Planning Board considered the provision of sewer service to the site. It was the determination of staff and the Planning Board that the provision of community sewer service, using a LDRC zone cluster option, allowed for an environmentally acceptable plan.

This determination should satisfy the condition of water and sewer service area category change requests. If you have any questions regarding this transmittal, please contact me at (301) 495 1323.

Thank you for your consideration of this matter.

Sincerely,

Dominic Quattrocchi Environmental Planning Division

Cc Robert Kronenberg, M-MCPPC Development Review Dot Pecson, MCDEP

Attachement: Planning Board Opinion



# Date Mailed: October 23, 2001 MONTGOMERY COUNTY DEPARTMENT OF PARK AND PLANNING

THE MARYLAND-NATIONAL CAPITAL PARK AND PLANNING COMMISSION

8787 Georgia Avenue Silver Spring, Maryland 20910-3760 Action: Approved Staff Recommendation
Motion of Comm. Bryant, seconded by
Comm. Wellington with a vote of 4-0;
Comms. Bryant, Holmes, Robinson and
Wellington voting in favor
Comm. Perdue absent

# MONTGOMERY COUNTY PLANNING BOARD

#### **OPINION**

Preliminary Plan 1-01086

NAME OF PLAN: MANDELL PROPERTY

On 06/18/01, PORTEN COMPANIES submitted an application for the approval of a preliminary plan of subdivision of property in the LDRC zone. The application proposed to create 14 lots on 72.40 acres of land. The application was designated Preliminary Plan 1-01086. On 10/01/01, Preliminary Plan 1-01086 was brought before the Montgomery County Planning Board for a public hearing. At the public hearing, the Montgomery County Planning Board heard testimony and received evidence submitted in the record on the application. Based upon the testimony and evidence presented by staff and on the information on the Preliminary Subdivision Plan Application Form, attached hereto and made a part hereof, the Montgomery County Planning Board finds Preliminary Plan 1-01086 to be in accordance with the purposes and requirements of the Subdivision Regulations (Chapter 50, Montgomery County Code, as amended) and approves Preliminary Plan 1-01086.

Approval, Pursuant to the FY 2002 Annual Growth Policy Alternative Review Procedures and Subject to the Following Conditions:

- Approval of this preliminary plan is limited to a maximum of fourteen units and the applicant shall pay to the Montgomery County Department of Finance the applicable Development Approval Payment (DAP), pursuant to the FY 2002 Annual Growth Policy prior to receipt of building permits
- 2) Compliance with the conditions of approval for the preliminary forest conservation plan. The applicant must satisfy all conditions prior to recording of plat(s) or MCDPS issuance of sediment and erosion control permits
- Record plat to provide for dedication of 70 feet of right-of-way for Batchellor's Forest Road
- 4) Record plat to show delineation of a Category I conservation easement over the area of stream valley buffer and forest conservation areas
- 5) Access and improvements as required to be approved by MCDPWT prior to issuance of access permit
- 6) Record plat to reference all common ingress/egress easements

- 7) All roads shown on the approved preliminary plan shall be constructed, by the applicant, to the full width mandated by the Approved and Adopted Master Plan, and to the design standards imposed by all applicable road codes.
- 8) Prior to recording of plat(s) Planning Board approval of waiver for over length cul-desac
- 9) No clearing, grading or recording of plat(s) prior to site plan approval
- 10) Final location of units to be determined at site plan
- All road right of way show on the approved preliminary plan shall be dedicated by the applicant, to the full width mandated by the Approved and Adopted Master Plan
- 12) This preliminary plan will remain valid for thirty-seven (37) months from the date of mailing of the Planning Board opinion. Prior to this date, a final record plat must be recorded for all property delineated on the approved preliminary plan, or a request for an extension must be filed
- 13) The Adequate Public Facility (APF) review for the preliminary plan will remain valid for sixty-one (61) months from the date of mailing of the Planning Board opinion
- 14) Other necessary easements
- 15) Prior to the submission of Site Plan, applicant to secure written sewer and water category change approval from Montgomery County Department of Environmental Protection



### MONTGOMERY COUNTY DEPARTMENT OF ENVIRONMENTAL PROTECTION WATERSHED MANAGEMENT DIVISION

Rockville Center - 255 Rockville Pike, Suite 120 - Rockville, Maryland 20850-4166 Telephone No. 240-777-7780 - FAX No. 240-777-7715

SUBDIVISION PLAN REVIEW: MNCPPC Development Review Committee (DRC) Comprehensive Water Supply and Sewerage Systems Plan Issues

DRC Meeting Date: 01/14/2002

MNCPPC File Number: 8-02019

Subdivison Plan Name: Mandell Property

Proposed Development: 14 single-family houses

approved 10/01/01

Watershed: Northwest Branch

Planning Area: Oiney

Location: Batchellor's Forest Road

Zoning: LDRC

Site Area: 72.4 acres

Engineer: Charles P. Johnson & Associates, Inc. 301-434-7000

07/16/2001

Water Supply and Sewerage Systems (as specified on the subject subdivision plan or plan application)

FROM MC DEP/DWWM

Proposed Water Supply:

Proposed Wastewater Disposal:

Community (public) WATER system

Community (public) SEWER system

Existing Service Area Categories: Water: W - 6\*

Sewer: S - 6°

Water/Sewer Plan Map Amendment: WSCCR 00A-OLN-05

Water Supply Comments:

Sewerage System Comments:

Pending; the sewerage system is consistent with the

CONDITIONAL sewer service area category

Pending; the water supply system is consistent with the

CONDITIONAL water service area category

\*Additional Comments: Prior preliminary plan 1-01086.

On November 27, 2001, MCDEP granted a conditional approval for W-3 and S-3 for this site under Administrative Delegation AD 2001-7. The condition for final approval for categories W-3 and S-3 is as follows:

'Maintain W-6 and S-6, with advancement to W-3 and S-3 conditioned on the Planning Board's approval of a preliminary plan using the LDRC zone cluster option."

Please advise us if preliminary plan no. 1-01086 is approved. If so, then M-NCPPC STAFF NEED TO NOTIFY THIS OFFICE WHETHERTHE PLANNING BOARD'S APPROVAL OF THE PLAN SATISFIES THE CONDITION CITED ABOVE. If so, then MCDEP will process the final category change approval.

1-01086 Mindell We appreciate that the proposed sewer outfalls to Batchellors Forest Rd, and not to the trunk sewer south of the site. However, we need to know if any consideration was given by either the engineer or WSSC to moving the point where the proposed sewer main crosses the stream north to coincide with the point where the proposed roadway also crosses the stream. This would reduce environmental stress on the stream by limiting disturbance of the wooded stream corridor to the private road crossing. Dopes the grade near the road preclude this option? We would appreciate a response to this issue before a final approval of the water and sewer category change is completed.

As noted before on MCDEP's 7/16/01 DRC comments regarding the preliminary plan, this site plan also does not show any existing or proposed water systems.

Prepared by: Alan Soukup/Dorothy Pecson

Date prepared:

01/10/2002

# MONTGOMERY COUNTY DEPARTMENT OF PERMITTING SERVICES WATER RESOURCES SECTION

255 Rockville Pike, 2nd Floor, Rockville, Maryland 20850-153

	Date: 4/14/06		
MEMO '	TO: Larry Ponsford, Site Planner Development Review Committee, MNCPPC	Application of the second	
FROM:	Blair Lough Water Resources Section, MCDPS	National Colonial Col	
SUBJE	Stormwater Management Concept Plan/100 yr.Floodplain Revie Site Plan # 8-02019 , Mandell Property Project Plan # Prellminary Plan # 1-01086 , DPS File # 1-01086 Subdivision Review Meeting of The subject plan has been reviewed to determine if it meets the		ulrements of Executive
Regulat followin	ine subject plan has been reviewed to determine in a mean and in 5-90 for stormwater management and Executive Regulation 108- g summarizes our findings:	2	M for floodplain. The
	NCEPT PLAN PROPOSED: site: Quantity Quality Both On-site/Joint Use Central (Regional): waived under 2.a.2.b. Existing Concept Approved		
	ver: Quantity Quality Both Approved on		
X Exe	mpt Other		
Inf	roposed: iltration	ter	
⊠ P study 0	rovide source of the 100Year Floodplain Delineation for DPS approval oct. 18, 2001.	ар	
	ubmit drainage area map to determine if a floodplain study (> or equal to 3 am Breach Analysis/100 yr.floodplain study: Approved U	0 a nde	Review:
Ad	SSION ADEQUACY COMMENTS: equate as submitted. evide verification of Downstream notification.		
Ap Inc Ho	MMENDATIONS:  prove as submitted with conditions (see comments below).  prove as submitted from with conditions (see comments below).  prove as submitted from with conditions (see comments below).  It for additional information. See below  mments/Recommendations:		
œ:	Steve Federline, Environmental Planning Division, MNCPPC		bli DRC site plan.03/01
Į.			

# Charles P. Johnson & Associates, Inc.

Planners

Engineers

Landscape Architects

Surveyors



Silver Spring, MD

Frederick, MD

Fairfax, VA

October 30, 2001

M-NCPPC 8787 Georgia Avenue Development Review Division Silver Spring, MD 20910-3760

Re: Mandell Property
Sidewalk Waiver Request

Dear Larry Ponsford,

On behalf of our client, Porten Companies, we would like to request a waiver for sidewalks along both sides of Street 'A' proposed in the Mandell Property. There are 14 lots on this site, each 2.00 acres and greater in size, and only 10 of the lots have direct access off of Street 'A'. It is our understanding that there will be very little pedestrian traffic along Street 'A', therefore sidewalks will not be needed.

If you have any questions or comments regarding these conditions, please call at 301-434-7000.

E de

Sincerel